

# Lahntal Bridge Limburg, A3



#### **SHORT DESCRIPTION**

Construction of a 450m long bridge.

#### **THE PROJECT**

The two superstructures of the 450 m long and 62 m high Lahntal Bridge each consist of two haunched, longitudinally prestressed hollow girders that were erected in cantilevered cantilevering.

#### **SERVICES IN DETAIL**

- 170 t external pre-tensioning
- 500 t internal pre-tensioning
- Installation, stressing and injection

### Procedure:

• BBV L15

#### • BBV L15E

# **FACTS**

Location	Limburg, Germany
Status	completed
Start of construction	January 2014
Completion	December 2016
Building owner	DEGES für Hessen Mobil
Contracting entity	Max Bögl
Planning	Büchting + Streit

# **SERVICES**

Post-tensioning system

Bridge construction



https://www.bbv-systems.com/en/projects/detail/ref/lahntal-bridge-limburg-a3/

Creation: 17.08.2025 08:30