



# **PalaisQuartier**



## **SHORT DESCRIPTION**

The construction of the southern part of the building is a special feature of the office tower.

### **THE PROJECT**

The usable area of the floors from the 7th floor is larger than on the levels below. This is achieved by making the ceilings cantilever from the 7th floor. The loads from the rising storeys in the area of the facade are directed to the center of the building on levels 7-12 through inclined mega-columns. The tensile forces generated at the deflection points are absorbed by type BBV L 7 tendons and anchored to the building core.

To limit deformations, the flat ceilings of the 12th - 32nd floors are designed with non-composite prestressing. 790 ST tendons of type BBV Lo4 are used, which are laid in free tendon positions.

#### **SERVICES IN DETAIL**

Shooting in, prestressing and extrusion of 17t prestressing steel with subsequent bond, type BBV L4, L6 and L7

Manufacture, delivery, prestressing and sealing of 35t tendons without bond type BBV Lo4

# **FACTS**

Location	Frankfurt a.M., Germany
Status	completed
Start of construction	January 2004
Completion	December 2011
Building owner	Frankfurt Hoch Vier GmbH
Contracting entity	Wayss & Freytag, Stuttgart
Planning	Weischede, Herrmann & Partner, Stuttgart

# **SERVICES**

Structural engineering



https://www.bbv-systems.com/en/projects/detail/ref/palaisquartier/

Creation: 03.12.2025 18:13