

## Ersatzneubau der Talbrücke Habichtswald



### SHORT DESCRIPTION

Tendons with a subsequent bond BBV L9 and BBV L15 as well as the external prestressing BBV L19E were installed here.

### THE PROJECT

The construction project is located in the Leeden municipality of Tecklenburg, in the Münster administrative district. In the first construction phase, the partial structure in the direction of Bremen was rebuilt.

The structure was constructed in 11 construction phases using the incremental launching method. The regular cycle is 24 m, the total length approx 252 m. Tendons with subsequent bond BBV L9 and BBV L15 as well as the external prestressing BBV L19E were installed in the box girder cross-section.

The prestressing steel work started in December 2016 and was successfully completed in May 2017. The superstructure of the second sub-structure in the direction of Münster was rebuilt in the course of 2018.

### FACTS

<b>Location</b>	Leeden , Germany
<b>Status</b>	completed
<b>Start of construction</b>	December 2016
<b>Completion</b>	May 2017

<b>Building owner</b>	Landesbetrieb Straßenbau Nordrhein-Westfalen, Regionalniederlassung Münsterland
<b>Contracting entity</b>	Gerdum u. Breuer Bauunternehmen GmbH, Bebra
<b>Planning</b>	Kinkel + Partner, Neu-Ise

## SERVICES

---

Post-tensioning system

Bridge construction



---

<https://www.bbv-systems.com/en/projects/detail/ref/replacement-construction-of-the-habichtswald-viaduct/>

Creation: 24.05.2026 13:52